21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

23. Tender forms can be obtained in the Executive Engineer, Office on payment of As. 4 for each copy.

Abstract Estimate for constructing combined Maternity-Ward and Child-Welfare Centre at Konanur, Arkalgud Taluk, Hassan District.

Sl. No.	Items of work	Quantity	Per	Rate Rs. a. p.
1	Earthwork excavation for foundation	151	C.yd.	0 3 0
2	Concrete stone jelly in lime mortar for foundation	802	C.ft.	0 3 6
3	Size stone in clay for foundation	4,740	,,	0 4 0
4	Superstructure brick in clay	4,527	,,	0 3 6
5	Providing cement concrete bed of 3″ thick instead of wall plate	139	,,	0 12 0
6	Burnt brick in lime mortar	383	,,	0 4 6
7	Roofing with Madras Terrace all over the building with 3″ brick jelly concrete in surki mortar and three course of flat tiles with necessary plastering to bottom and top, etc., complete	39.44	Sqr.	35 0 0
8	Teakwood work wrought and put up with two coats of wood oiling	295	C.ft.	4 12 0
9	Providing and fixing R.C.C. ventilators over doors and windows	50	S.ft.	1 0 0
10	Do R.C.C. Chajja works to windows alround 4″ thick and $2\frac{1}{2}$ projection including plastering, etc., complete	271	,,	0 12 0
11	Brick in mortar cornice alround the building 9″ thick as per design	400	R.ft.	0 8 0
12	Brick in mortar parapet wall of $1\frac{1}{2}$′ high alround the building including plastering, etc., complete	380	,,	1 0 0
13	Plastering with chunam mortar	110.51	Sqr.	3 8 0
14	White washing two coats	110.51	,,	0 4 0
15	Cement pointing to basement	7.54	,,	3 8 0
16	Flooring with $1\frac{1}{2}$″ thick cement concrete with coloured cement plaster on 3″ lime mortar concrete bed, etc., complete	27.86	Sqr.	20 0 0
17	Providing and fixing R. S. girders including hoisting, etc., complete with bed plate	6.3	Cwt.	13 0 0
18	Constructing brick masonry pillars in cement mortar with necessary bases capitals and bond stones, etc., complete	254	C.ft.	0 10 0
19	Burnt stone slabs 6″ thick dressed and fixed	949	S.ft.	0 8 0
20	Teakwood doors 3″×4″ frames $1\frac{1}{4}$″ thick panelled shutters zinc door locks with iron fittings, etc., complete including glazed ventilators and painting complete	504	S.ft.	2 0 0
21	Teakwood panelled windows with 3″×4″ frames and $1\frac{1}{4}$″ thick shutters and parliamentary hinges with necessary ventilators including iron fittings, etc., complete with painting	547	S.ft.	2 0 0
22	Rainwater down take pipes of galvanized iron including fixing with necessary bendings, etc., complete	144	R.ft.	0 6 0
23	Water supply and sanitary fittings	L. S.	..	300 0 0
24	Boxing the girders with cement mortar, etc., complete	20	R.ft.	1 0 0

P. SUBBA RAO,
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 17th October 1939.

The attention of the public is drawn to the tender notification published in pages 2140-2141, Part VI of the *Mysore Gazette*, dated 26th October 1939, calling for tenders for "Opening out a high level feeder channel from Mallapur tank, Regd. No. 465-505 of Shikarpur Taluk."

The last date fixed for the receipt of tenders in this office is 6 P.M. on the 15th November 1939.

M. VENKATAKRISHNA RAO,
Executive Engineer.